



Publication Year	2017
Acceptance in OA	2024-06-26T10:07:59Z
Title	Metis Performance Verification and Calibration Procedure
Authors	NICOLINI, Gianalfredo, FINESCHI, Silvano
Handle	http://hdl.handle.net/20.500.12386/35252
Volume	METIS-OATO-PRO-002

**Metis INSTRUMENT
for the
Solar Orbiter Mission**

**Test Report
Metis Performance Verification and Calibration Procedure**

Principal Investigator:

Ester Antonucci
INAF – Astrophysical Observatory of Turin, Torino, Italy

and the METIS Consortium:

Astronomical Institute – Academy of Sciences of the Czech Republic
CNR - Institute for Photonics and Nanotechnology, Padova, Italy
INAF – IASF, IAPS, OAA, OACN, OACt, OAPa, OATo, OATs, Italy
Laboratoire d’Astrophysique de Marseille, France
Max-Planck-Institute für Sonnensystemforschung, Germany
Naval Research Laboratory, USA
Politecnico of Turin, Italy
Universities of Florence, Padua, Italy
University of Athens, Greece



prepared by G. Nicolini – S. Fineschi

approved by E. Antonucci
reference METIS-OATO-PRO-002
issue 1
revision 10
date of issue 03-MAY-2017

Page intentionally left blank

Distribution

Name	Organisation
Marco Castronuovo	ASI – Agenzia Spaziale Italiana Viale Liegi, 26 - 00198 Roma - ITALY
Filippo Marliani	ESA/ESTEC (SCI-P) + P.O. Box 299 1 (part VI) 2200 AG Noordwijk The Netherlands
Daniel Müller	ESA/ESTEC (SCI-SM) + P.O. Box 299 1 (part VI) 2200 AG Noordwijk The Netherlands
Philippe Kletzkine	ESA/ESTEC (SCI-P) + P.O. Box 299 1 (part VI) 2200 AG Noordwijk The Netherlands

Change Log

date	issue	revision	Paragraphs	reason for change
22/03/2017	1	0	All	First Issue
28/03/2017	1	1		Added missing procedures
30/03/2017	1	2	5.1.1 5.1.2 5.1.3 5.1.4	related procedures finalised
1/04/2017	1	3	5.1.3 5.1.4 3.8.1 3.8.2	related procedures finalised
04/04/2017	1	4		
06/04/2017	1	5	3.6.1 3.6.2	related procedures finalised
11/04/2017	1	6	3.8.2	Revised and finalised
			3.8.4	added
19/04/2017	1	7	3.6.1, 3.6.2, 3.6.3, 3.6.4, 3.6.5	Revised and finalized
			3.6.5.1, 3.6.5.2 3.6.5.3, 3.6.5.4 3.6.5.5, 3.6.5.6 3.6.5.7, 3.6.5.8 3.9.1.1, 3.9.1.2, 3.9.1.1, 3.9.1.2,	added
21/04/2017			3.5.2, 3.5.6	added
29/04/2017	1	9	3.8.5	added
			3.8.3	modified

date	issue	revision	Paragraphs	reason for change
			3.5.6	modified
03/05/2017	1	10	3.5.5	modified and finalised
			3.5.7	modified and finalised
			3.8.3	modified and finalised

Table of Contents

1	INTRODUCTION.....	8
1.1	Scope of the document	8
1.2	Optical Payload System (OPSys) Facility	8
2	TEST APPROACH.....	9
2.1	Instrument configuration and de-configuration - Giana.....	9
2.2	Performance Verification - Giana.....	9
2.3	Coronagraphs Test.....	9
3	PROCEDURES.....	10
3.1	Initialization and configuration	10
3.1.1	Instrument configuration from OFF to OPS mode.....	10
3.1.2	Instrument de-configuration from OPS, SETUP or DIAG mode to OFF	14
3.1.3	Instrument configuration from OFF to DIAG mode	16
3.1.4	Cool-down and warm-up procedures	20
3.1.5	Metis – ISVL sun simulator alignment procedure	20
3.1.5.1	Required OGSE	20
3.1.5.2	Alignment procedure.....	20
3.1.5.2.1	Align theodolite on SPOCC reference axis.....	20
3.1.5.2.2	METIS – SPOCC mutual alignment.....	21
3.1.5.2.3	METIS clockwise rotation of 2°.2 with respect to the reference axis	21
3.1.5.2.4	METIS counter-clockwise rotation of 2°.2 with respect to the reference axis	21
3.2	Stress tests.....	22
3.2.1	VHDL test case 01: VL-FP@ 1s acquisition (binning).....	22
3.2.2	VHDL test case 02: VL-FP@ 1s acquisition (masking).....	26
3.2.3	VHDL test case 03: VL-pB-4Pol@ 15s & UV_Analog@ 1s acquisition (masking)	30
3.2.4	VHDL test case 04: VL-pB@ 15s + UV-PC-List acquisition	37
3.2.5	VHDL test case 05: VL-tB@ 20s + UV-Analog acquisition.....	44
3.2.6	VHDL test case 06: VL-tB@ 20s + UV-PC acquisition	51
3.3	Duration e data volume test.....	60
3.3.1	RSW - Fluctuation (A – Nominal as SPR)	60
3.3.2	RSW - Fluctuation (B – deltaQ=20 TBC):	64
3.3.3	RSW - Fluctuation (C– deltaQ=50 TBC):	68
3.3.4	RSW - MAGTOP.....	72
3.3.5	RSW - WIND (A – Sun @ 0.5AU).....	81
3.3.6	RSW - WIND (B – Sun @ 1AU).....	86
3.3.7	RSW - GLOBAL (A - Sun @ 0.5AU)	91
3.3.8	RSW - GLOBAL (B - Sun @ 1AU)	96
3.3.9	RSW - LT-Config	101
3.4	Flag triggering and verification	110
3.4.1	CME Flag	110
3.4.2	Sun Disk Monitor Flag -TBC	110
3.5	Scientific algorithms and compression verification.....	112

3.5.1	Detector Noise	112
3.5.2	UV Transient investigation.....	122
3.5.3	UV NDIT-NACQ	142
3.5.4	PCU study – I – minimum DIT.....	159
3.5.5	PCU study – II – PCU Offset Map Acquisition and verification	166
3.5.6	PCU study – III – PCU Acquisition and functional verification	178
3.5.7	Compression.....	207
3.5.8	Compression NCR (Pre_Bands verification).....	215
3.6	Stray Light	219
3.6.1	Stray light normalization and radiometry (with LED source).....	219
3.6.2	Stray Light Test Sun-center pointing	225
3.6.3	Stray Light Test with Sun-pointing steps up to +0.8°	235
3.6.3	Stray Light Test with Sun-pointing steps up to +0.8° – Date:.....	236
3.6.4	Stray Light Test with Sun-pointing steps up to -0.8°	248
3.6.4	Stray Light Test with Sun-pointing steps up to -0.8° – Date:.....	249
3.6.5	Stray Light Test for IEO-IO centering°	261
3.6.5.1	Stray Light Test for IEO-IO centering – X-motor 60 engineering units cw	262
3.6.5.1	IEO-IO centering – X-motor 60 eng. units cw – Date:.....	262
3.6.5.2	Stray Light Test for IEO-IO centering – X-motor 60 engineering units ccw.....	273
3.6.5.2	IEO-IO centering – X-motor 60 eng. units ccw – Date:.....	273
3.6.5.3	Stray Light Test for IEO-IO centering – Y-motor 60 engineering units cw	285
3.6.5.4	Stray Light Test for IEO-IO centering – Y-motor 60 engineering units ccw.....	296
3.6.5.5	Stray Light Test for IEO-IO centering – X-motor and Y-motor by 43 engineering units cw	307
3.6.5.6	Stray Light Test for IEO-IO centering – X-motor and Y-motor by 43 engineering units ccw	319
3.6.5.7	Stray Light Test for IEO-IO centering – X-motor by 43 engineering units cw and Y-motor by 43 engineering units ccw.....	331
3.6.5.8	Stray Light Test for IEO-IO centering – X-motor by 43 engineering units ccw and Y-motor by 43 engineering units cw	343
3.7	VL Calibration	355
3.7.1	Dark Measurement.....	355
3.7.2	Vignetting Function	360
3.7.3	Imaging performance & Radiometric.....	365
3.8	UV Calibration.....	376
3.8.1	UV Signal tuning– Analog Mode	376
3.8.2	Spatial resolution – Analog Mode.....	400
3.8.3	Spatial resolution – Photon Counting Mode.....	420
3.8.4	UV Signal tuning– HV ramp-up dry run	439
3.8.5	Spatial resolution – HV screen scan in Analog Mode	475
3.9	Polarimetric response.....	497
3.9.1	Flat Field (in air).....	497
3.9.1.1	Setup and Dark	498
3.9.1.2	Pre-Polarizer at determined position (5° steps).....	501
3.9.1.3	Polarized acquisitions	514
3.9.1.4	Pre-Polarizer at determined position (10° steps).....	517
3.9.2	Total Brightness characterization.....	525
3.9.3	Polarimetric response in vacuum (LED source)	526
3.9.3.1	Setup and Dark	527
3.9.3.2	Polarizer at arbitrary position	531
3.9.3.3	Polarized acquisitions	544
4	DOCUMENT REFERENCES	548
4.1	Reference Documents.....	548

5	ACRONYMS	549
	APPENDIX A – TSC SCRIPTS USED.....	550
	APPENDIX B – SPOCC ACTUATOR RANGES.....	551
	ANNEX C.....	552

1 Introduction

1.1 Scope of the document

The scope of this document is to provide the necessary instructions for the performance verification and for the ground calibrations of Metis PFM.

1.2 Optical Payload System (OPSys) Facility

Breve descrizione + fare riferimento ai documenti applicabili