



Publication Year	2017
Acceptance in OA	2021-04-16T09:14:12Z
Title	Comet 67P outbursts and quiescent coma at 1.3 au from the Sun: dust properties from Rosetta/VIRTIS-H observations
Authors	Bockelée-Morvan, D., RINALDI, GIOVANNA, Erard, S., Leyrat, C., CAPACCIONI, FABRIZIO, Drossart, P., FILACCHIONE, GIANRICO, MIGLIORINI, Alessandra, Quirico, E., Mottola, S., Tozzi, G., Arnold, G., Biver, N., Combes, M., Crovisier, J., LONGOBARDO, ANDREA, Blecka, M., CAPRIA, MARIA TERESA
Publisher's version (DOI)	10.1093/mnras/stx1950
Handle	http://hdl.handle.net/20.500.12386/30767
Journal	MONTHLY NOTICES OF THE ROYAL ASTRONOMICAL SOCIETY
Volume	469

Comet 67P outbursts and quiescent coma at 1.3 au from the Sun: dust properties from *Rosetta*/VIRTIS-H observations

D. Bockelée-Morvan,¹★ G. Rinaldi,² S. Erard,¹ C. Leyrat,¹ F. Capaccioni,² P. Drossart,¹ G. Filacchione,² A. Migliorini,² E. Quirico,³ S. Mottola,⁴ G. Tozzi,⁵ G. Arnold,⁴ N. Biver,¹ M. Combes,¹† J. Crovisier,¹ A. Longobardo,² M. Blecka⁶ and M.-T. Capria²

¹LESIA, Observatoire de Paris, PSL Research University, CNRS, Sorbonne Universités, UPMC Univ. Paris 06, Univ. Paris-Diderot, Sorbonne Paris Cité, 5 place Jules Janssen, F-92195 Meudon, France

²INAF-IAPS, Istituto di Astrofisica e Planetologia Spaziali, via del fosso del Cavaliere, 100, I-00133 Rome, Italy

³CNRS, Institut de Planétologie et d'Astrophysique de Grenoble, Université Grenoble Alpes, 414 rue de la Piscine, BP53, F-38041 Grenoble, France

⁴Deutsches Zentrum für Luft- und Raumfahrt (DLR), Institute for Planetary Research, Rutherfordstrasse 2, D-12489 Berlin, Germany

⁵INAF, Osservatorio Astrofisico di Arcetri, Largo E. Fermi 5, I-50125 Firenze, Italy

⁶Space Research Centre, Polish Academy of Sciences, Bartycka 18a, PL-00716 Warsaw, Poland

Accepted 2017 July 27. Received 2017 July 26; in original form 2017 May 12

ABSTRACT

We present 2–5 μm spectroscopic observations of the dust coma of 67P/Churyumov–Gerasimenko obtained with the VIRTIS-H instrument onboard *Rosetta* during two outbursts that occurred on 2015, 13 September 13.6 h UT and 14 September 18.8 h UT at 1.3 au from the Sun. Scattering and thermal properties measured before the outburst are in the mean of values measured for moderately active comets. The colour temperature excess (or superheat factor) can be attributed to submicrometre-sized particles composed of absorbing material or to porous fractal-like aggregates such as those collected by the *Rosetta in situ* dust instruments. The power-law index of the dust size distribution is in the range 2–3. The sudden increase of infrared emission associated with the outbursts is correlated with a large increase of the colour temperature (from 300 to 630 K) and a change of the dust colour at 2–2.5 μm from red to blue colours, revealing the presence of very small grains (≤ 100 nm) in the outburst material. In addition, the measured large bolometric albedos (~ 0.7) indicate bright grains in the ejecta, which could either be silicatic grains, implying the thermal degradation of the carbonaceous material, or icy grains. The 3 μm absorption band from water ice is not detected in the spectra acquired during the outbursts, whereas signatures of organic compounds near 3.4 μm are observed in emission. The H₂O 2.7 μm and CO₂ 4.3 μm vibrational bands do not show any enhancement during the outbursts.

Key words: comets: general – comets: individual: 67P/Churyumov-Gerasimenko – infrared: planetary systems.

1 INTRODUCTION

The *Rosetta* mission of the European Space Agency accompanied comet 67P/Churyumov–Gerasimenko between 2014 and 2016 as it approached perihelion (2015 August 13) and receded from the Sun. The suite of instruments on the orbiter and on the Philae lander provided complementary information on the physico-chemical

properties of the nucleus, and inner coma gases and dust, from which questions related to the formation of 67P and origin of its primary constituents could be studied (Davidsson et al. 2016; Fulle et al. 2016a). *Rosetta* also provided the first opportunity to study closely how cometary activity proceeds, evolves with seasons, and affects the nucleus surface properties (El-Maarry et al. 2017).

One of the striking discoveries of *Rosetta* has been the repeatability of jets from one rotation to another, growing and fading according to solar illumination and originating from cliffs, fractures and pits (Vincent et al. 2016a). Strong similarities between the near-nucleus dust and water distributions were observed, indicating that

* E-mail: Dominique.Bockelee@obspm.fr

† Deceased.

dust release is associated with water sublimation (Fink et al. 2016; Rinaldi et al. 2016). Other manifestations of cometary activity are the detection of morning jets (Shi et al. 2016) and transient events, the so-called outbursts. The cameras of the Optical, Spectroscopic and Infrared Remote Imaging System (OSIRIS) detected not less than 34 outbursts during the 3 months encompassing the perihelion passage, one every 2.4 rotations, with three main plume morphologies: a narrow jet, a broad fan and more complex plumes featuring both previous types together (Vincent et al. 2016b). Grün et al. (2016) review observations by nine *Rosetta* instruments of a dusty outburst which occurred on 2016 February 19, when the comet was at 2.4 au from the Sun. Gaseous outbursts with no dust counterparts were also observed (Feldman et al. 2016).

A few outbursts have been observed with the Visible InfraRed Thermal Imaging Spectrometer (VIRTIS) onboard *Rosetta* (Coradini et al. 2007), in both VIRTIS-H and VIRTIS-M channels. This paper presents the analysis of VIRTIS-H infrared (2–5 μm) spectra acquired during two dusty outbursts that occurred on 2015 September 13 and 14, i.e. about one month after perihelion. The complementary spectro-imaging observations of these outbursts undertaken with VIRTIS-M in the visible spectral range are presented by Rinaldi et al. (in preparation). The two outbursts have very different morphologies, with the September 13 outburst being strongly radially collimated, whereas the September 14 outburst extended laterally (Rinaldi et al., in preparation). The VIRTIS-H spectra cover a range where both the dust-scattered sunlight and the dust thermal emission can be studied, to derive constraints on the properties of the dust particles present in the ejecta cloud. The 2–5 μm spectral range also covers vibrational bands of important gases, such as H_2O and CO_2 , so that the gaseous counterpart of the outbursts can be potentially studied.

Section 2 presents the observations. In Section 3, the methodology to reduce and analyse the VIRTIS-H spectra, and the retrieved spectral properties are given. Section 4 presents the models used to interpret the spectra, and the constraints derived on the dust size distribution and composition. Attention is given to the properties of the dust coma both before the outburst and in the outburst ejecta. The gaseous counterpart is discussed in Section 5. A discussion follows in Section 6.

2 OUTBURST OBSERVATIONS

VIRTIS obtained spectra of the coma of comet 67P at the time of two important outbursts on 2015 September 13 and 14. VIRTIS is composed of two channels: VIRTIS-M, a spectro-imager operating both in the visible (0.25–1 μm) and infrared (1–5 μm) ranges at moderate spectral resolution ($\lambda/\Delta\lambda = 70\text{--}380$), and VIRTIS-H, a cross-dispersing spectrometer providing spectra with higher spectral resolution capabilities ($\lambda/\Delta\lambda = 1300\text{--}3500$) in eight orders of a grating covering the range 1.9–5.0 μm (Drossart et al. 2000; Coradini et al. 2007).

As for most *Rosetta* instruments, the line of sight of VIRTIS-H is along the Z-axis of the spacecraft (S/C). The instantaneous field of view (FOV) of this point instrument is $0.58 \times 1.74 \text{ mrad}^2$ (the larger dimension being along the Y-axis). Details on the calibration process are given in Bockelée-Morvan et al. (2016). The version of the calibration pipeline is CALIBROS-1.2-150126.

The September 13 and 14 outbursts were first identified in images obtained by VIRTIS-M at 0.55 μm , showing unusual coma morphologies (Rinaldi et al., in preparation). In VIRTIS-H data, these outbursts are characterized by a sudden increase of the dust continuum, both in reflected light (<3 μm) and thermal emission




Figure 1. VIRTIS-H spectra acquired on 2015 September 13 (top) and September 14 (bottom). In each plot, the upper and lower spectrum were acquired during the outburst and before the outburst, respectively. For September 13, the time intervals are 13.4003–13.6028 and 13.7125–13.7968 h UT. For September 14, the time intervals are 18.8060–18.8248 and 18.8632–18.8838 h UT. Outburst spectra were shifted by $+0.01 \text{ W m}^{-2} \mu\text{m}^{-1} \text{ sr}^{-1}$. Median smoothing (with dimension 20 outside the molecular bands) was applied. Radiance values in the range 4.2–5 μm were corrected as described in Section 3.2, with $s = 0.2$. Overplotted, in red, is the best model fit with the retrieved parameters given in Table 2.

(>3 μm) (Figs 1 and 2), followed by a gentle decrease lasting a few minutes to tens of minutes. Table 1 provides some details on the two VIRTIS-H observations that are considered: identification number of the data cube (Obs. Id), start time and duration of the observations, number of acquisitions and acquisition duration. For these observations, the exposure time was 3 s, and the dark rate was 4 (one dark image every four acquisitions). Frame summation was performed on-board, by summing pairs of acquisitions, so that the duration of each acquisition in the calibrated data cubes is 6 s.

Geometric parameters are provided in Table 1: the distance of *Rosetta* to the comet $\Delta(\text{S/C})$, the heliocentric distance r_h , the phase angle and some information on the position of the FOV with respect to the comet and comet–Sun line, that is its distance ρ to comet centre, and the position angle PA in the XY plane. In our convention (see Bockelée-Morvan et al. 2016), the Sun is at PA = 270°,




Figure 2. Time evolution of the radiance at 2.46, 3.85 and 4.60 μm on 2015 September 13 (top) and September 14 (bottom). The dashed lines in the bottom figure delimit the period when *Rosetta* was slewing. Outside this time range the FOV was staring at a fixed position (see text).

which means that the FOV during the measurements ($\text{PA} = 265^\circ$, Table 1) was almost along the comet–Sun line. For the September 13 data cube, the FOV was stared at a fixed distance in inertial frame ($\rho = 3.61$ km). On the other hand, for the September 14 data cube, several (actually 12) stared positions were commanded along the $-X$ direction (i.e. towards Sun), moving back and forth from 4.82 to 9.32 km from comet centre. Fortunately, the recorded September 14 outburst occurred just after the beginning of a stared sequence at $\rho = 4.835$ km which started at 18.804 164 h UT and ended at

Table 1. Log of VIRTIS-H observations.

Obs Id	Start time (UT)	Obs length (h)	Nb acq.	Acq. length ^a (s)	r_h (au)	$\Delta(\text{S/C})$ (km)	phase ($^\circ$)	Pointing ^b ρ (km)	PA ($^\circ$)
00400765976	2015-09-13T11:46:19.3	3.64	1728	6	1.302	312	108	3.61	265
00400873041	2015-09-14T17:30:48.1	3.91	1856	6	1.306	315	99	4.82–9.32	265

Notes. ^aThis is a factor of 2 higher than the exposure time of 3 s, because of onboard frame summing.

^bDistance to comet centre (ρ) and position angle PA of the FOV ($\text{PA}(\text{Sun}) = 270^\circ$). During September 14 cube acquisition, the FOV was stared at four different distances in the range indicated.

18.927 901 h UT. The next stared sequence at $\rho = 6.319$ km started at 19.008 519 h UT, when some outburst material was still crossing the FOV (Fig. 2). Between the two sequences, the *Rosetta* spacecraft was slewing and the FOV was at intermediate distances.

The time, duration and strength of the outbursts are given in Table 2. The duration is computed using the time at which the radiance returned at the pre-outburst value. The September 13 main outburst started at 13.645 UT, and was also observed with the Alice UV spectrometer (Feldman, private communication). The time evolution of the radiance then followed a complex pattern suggesting consecutive events (at least three, Fig. 2). This outburst, which lasted about 30 min, was followed by two ‘mini outbursts’, which occurred about 40 and 82 min later. The September 14 outburst started at 18.828 UT, and can be qualified as a major outburst since the dust thermal emission at 4.6 μm increased by a factor of ~ 7 with respect to the pre-outburst value. All the outbursts are characterized by a sudden increase of the dust emission, peaking a few minutes later, followed by a smooth decrease of the emission until it comes back to the pre-outburst value. Another common feature is the change in the ratio of the intensities at 3.6 and 3.85 μm . The pre-outburst values of $I_{4.6 \mu\text{m}}/I_{3.85 \mu\text{m}}$ are ~ 2 . When outburst material is within the FOV, this ratio is lower, reaching values of 1.4 and 1.7 for the September 13 and 14 main outbursts, respectively, and 1.9 for the last mini outburst. This indicates that the particles emitted during the outbursts have properties that are different from the usual dust. In particular, this trend would be consistent with higher grain temperatures in the outburst ejecta. The different light curves observed in reflected and thermal emission on September 14 (Fig. 2) are another indication of different dust properties that changed with time.

3 PROPERTIES OF DUST EJECTA

3.1 Approach for dust spectral properties retrievals

Gehrz & Ney (1992) described two empirical parameters derivable from the dust infrared spectral energy distribution (SED) measured in cometary atmospheres that are related to the optical properties of the grains contributing importantly to the SED. These parameters are the superheat S_{heat} and the bolometric phase-dependent albedo $A(\theta)$, where θ is the scattering angle.

The superheat is defined as the ratio of the observed colour temperature T_{col} to the equilibrium temperature T_{equ} at the heliocentric distance r_h of the comet:

$$S_{\text{heat}} = \frac{T_{\text{col}}}{T_{\text{equ}}} = \frac{T_{\text{col}}}{278r_h^{-0.5}}. \quad (1)$$

The bolometric albedo is defined as

$$A(\theta) = \frac{f(\theta)}{1 + f(\theta)}, \quad (2)$$

Table 2. Properties of outburst and pre-outburst spectra.

Date	Init/peak time ^(a) (h)	Duration ^(b) (min)	$I^{\max}/I^{\text{pre}(c)}$	T_{col} (K)	S_{heat}	$A(\theta)$	S'_{col} per cent/100 nm
<i>Total spectra</i>							
September 13 main outburst	13.645/13.748	26.6	3.0	429 ± 9^d	1.76 ± 0.04^d	0.51 ± 0.02^d	1.0 ± 0.3^d
September 13 mini-outburst 1	14.308/–	6.8	1.1	–	–	–	–
September 13 mini-outburst 2	15.007/15.021	9.6	1.5	356 ± 9^e	1.46 ± 0.04^e	0.29 ± 0.09^e	2.2 ± 0.4^e
September 14 outburst	18.828/18.865	12.2	7.3	561 ± 12^f	2.31 ± 0.05^f	0.54 ± 0.01^f	-2.6 ± 1.0^f
<i>Outburst material</i>							
September 13 main outburst	–	–	–	528 ± 10^d	2.17 ± 0.04^d	0.67 ± 0.01^d	-2.1 ± 0.1^d
September 13 mini-outburst 2	–	–	–	549 ± 12^e	2.25 ± 0.05^e	0.62 ± 0.04^e	-2.2 ± 0.7^e
September 14 outburst	–	–	–	621 ± 12^f	2.55 ± 0.05^f	0.56 ± 0.01^f	-9.1 ± 1.4^f
September 13 pre-outburst	–	–	–	297 ± 6^g	1.22 ± 0.02^g	0.13 ± 0.02^g	2.6 ± 0.3^g
September 14 pre-outburst	–	–	–	293 ± 8^h	1.20 ± 0.03^h	0.13 ± 0.02^h	2.3 ± 0.4^h

Notes. ^aMeasured at 4.6 μm (same values for 3.85 μm).

^bDefined by the time at which the intensity returned at the pre-outburst value.

^cMeasured at 4.6 μm .

^dFrom spectrum averaging acquisitions 921–961 (13.7125–13.7968 h UT).

^eAcquisitions 1541–1551 (15.0220–15.0426 h UT).

^fAcquisitions 641–646 (18.8632–18.8735 h UT).

^gAcquisitions 773–869 (13.4003–13.6028 h UT).

^hAcquisitions 614–623 (18.8060–18.8248 h UT).

with

$$f(\theta) = \frac{[\lambda F_{\text{scatt}}(\lambda)]^{\lambda_{\text{max,scatt}}}}{[\lambda F_{\text{therm}}(\lambda)]^{\lambda_{\text{max,therm}}}} \quad (3)$$

The quantities $[\lambda F_{\text{scatt}}(\lambda)]^{\lambda_{\text{max}}}$ and $[\lambda F_{\text{therm}}(\lambda)]^{\lambda_{\text{max}}}$ are the apparent intensities (times the wavelength) measured at the maxima of the Planck function in the scattered and thermal part of the spectrum, respectively. $A(\theta)$ is referred to as the bolometric albedo, since it is approximately equal to the ratio between the scattered energy by the coma to the total incident energy (Woodward et al. 2015).

The parameters S_{heat} and $A(\theta)$ have been measured in several comets (e.g. Mason et al. 2001), including during outbursts (Yang, Jewitt & Bus 2009), and can be retrieved from VIRTIS-H spectra (Fig. 1) by fitting the SED by the sum of the solar radiation scattered by coma dust grains, and a variable temperature blackbody describing the thermal emission from absorbing grains.

We modelled the scattered flux as

$$F_{\text{scatt}}(\lambda) = \frac{F_{\odot}(\lambda)g_{\text{col}}(\lambda)K_{\text{scatt}}}{r_{\text{h}}^2}, \quad (4)$$

where $F_{\odot}(\lambda)$ is the solar irradiance at $r_{\text{h}} = 1$ au. K_{scatt} is a coefficient determined in the fitting process which is function of both the total geometric cross-section of the dust grains within the FOV and the scattering properties of the individual grains, such as the scattering phase function, and their scattering efficiency (Appendix A). $g_{\text{col}}(\lambda)$ is a factor which describes the wavelength dependence of dust scattering. $g_{\text{col}}(\lambda)$ is expressed as

$$g_{\text{col}}(\lambda) = \left(\frac{\lambda}{\lambda_{\text{ref}}} \right)^{-\alpha_c} \quad (5)$$

where λ_{ref} is taken equal to 2 μm . From the spectral index α_c , one can deduce the reflectivity gradient S'_{col} , also called the dust colour and usually expressed in per cent per 100 nm. VIRTIS-H spectra provide information on the spectral index between 2 and 2.5 μm . The dust colour in this range is computed according to

$$S'_{\text{col}} = (2/500) \times \frac{g_{\text{col}}(2.5 \mu\text{m}) - g_{\text{col}}(2.0 \mu\text{m})}{g_{\text{col}}(2.5 \mu\text{m}) + g_{\text{col}}(2.0 \mu\text{m})}. \quad (6)$$

The thermal radiation is modelled as

$$F_{\text{therm}}(\lambda) = B(\lambda, T_{\text{col}})K_{\text{therm}}, \quad (7)$$

where $B(\lambda, T_{\text{col}})$ is the Planck function, and T_{col} and K_{therm} are free parameters determined by the fitting routine. K_{therm} is the absorption cross-section which depends on the absorption properties of the individual grains, and the emitting cross-section within the FOV. In calculations, this parameter is assumed to be constant in the wavelength range covered by VIRTIS-H.

The fit of the observed spectra was performed by means of the χ^2 minimization algorithm of Levenberg–Marquardt, with altogether up to five free parameters: the dust parameters K_{scatt} , K_{therm} , T_{col} and α_c , and a multiplying coefficient $K_{\text{H}_2\text{O}}$ to a synthetic water emission profile computed as described in Bockelée-Morvan et al. (2016) which was added to the ‘scattering+thermal’ dust model. Indeed, the water emission band at 2.7 μm occupies a large fraction of the spectrum in the range where both the scattered and thermal dust emissions are significant (Fig. 1). The spectral regions covering the CO_2 and $^{13}\text{CO}_2$ bands (4.2–4.5 μm) and the CH stretches (3.3–3.6 μm) were masked in the fitting process.

The wavelength range of VIRTIS-H does not cover the maxima of the scattered and thermal dust spectra. Therefore, our determination of $A(\theta)$ is done using extrapolation. For computing $[F_{\text{scatt}}(\lambda)]^{\lambda_{\text{max}}}$ ($\lambda_{\text{max}} \sim 0.5 \mu\text{m}$), we took into account the change of the dust colour with wavelength, and assumed $S'_{\text{col}} = 11$ per cent/100 nm from 0.5 to 0.9 μm and $= 1.7$ per cent/100 nm from 0.9 to 2.0 μm , as determined by Rinaldi et al. (2016) for comet 67P at $r_{\text{h}} \sim 1.8$ –2.2 au. The maximum of the dust thermal emission was derived from the maximum of $F_{\text{therm}}(\lambda)$ (equation 7), using the derived T_{col} and K_{therm} . This approach provides approximate values for $A(\theta)$. Concerning the thermal part, the colour temperature is a function of wavelength as a result of wavelength-dependent and size-dependent dust emissivities, whereas we are assuming that T_{col} is constant. This might affect retrievals when T_{col} is low, the Planck function peaking then well above 5 μm ($\sim 10 \mu\text{m}$ for 300 K). Concerning the reflected part, sources of errors are the effective dust colours from 0.5 to 2 μm , which may differ from the assumptions, especially for spectra acquired during the outbursts. From VIRTIS-M data, the




Figure 3. VIRTIS-H spectrum acquired on September 13 from 13.7125 to 13.7968 h UT. In the top spectrum, radiance values measured in the range 4.2–5 μm were corrected as described in Section 3.2, with $s = 0.2$. This correction is not applied in the bottom spectrum. Overplotted, in red, are the best model fits.

dust colour measured between 0.45 and 0.75 μm remained in the range 10–15 per cent/100 nm and 6–12 per cent/100 nm during the time interval corresponding to the September 13 and 14 VIRTIS-H data, respectively (Rinaldi et al., in preparation), with the lowest values corresponding to the outburst material. However, no data are available concerning the dust colour from 1 to 2 μm . Therefore, checks were done by comparing the extrapolated $F_{\text{scatt}}(586 \text{ nm})$ to measurements obtained at 586 nm using VIRTIS-M at the same location and time than VIRTIS-H. We concluded that the bolometric albedos derived by our method are correctly estimated.

3.2 Data analysis

Model fitting was applied to spectra obtained by averaging several acquisitions (6–11 at times showing outburst-related excess signal, up to 50 during quiescent states). VIRTIS-H spectra are sampled over 3456 spectral channels, 432 in each grating order. Since adjacent orders cover common wavelength ranges, we have carefully selected the most reliable channels. In particular, the short wavelength range of each order is often contaminated by instrumental straylight (Bockelée-Morvan et al. 2016) and was not considered.

Resulting spectra present inconsistent radiance values in the overlapping regions of the diffraction orders. The discrepancies are within 15 per cent for non-outburst data, and within 10 per cent for outburst data, and cannot be only attributed to instrumental straylight. For example, the mean intensity between 2.85 and 2.95 μm is lower for order 2 than for order 3, whereas straylight would produce the opposite. More problematic is the junction between orders 0 and 1 (4.2 μm). For acquisitions acquired during the outbursts (i.e. higher fluxes), radiance values are lower in order 0 than in order 1, and the discrepancy between the two orders increases with increasing signal (reaching values up to 10 per cent). In addition, model fitting shows that the continuum emission above 4.2 μm (i.e. in order 0) is distorted, as illustrated in Fig. 3 for a spectrum acquired during an outburst. The distortion is akin to a change of the bending of the spectrum, resulting in a higher flux than expected above $\sim 4.5 \mu\text{m}$, and a lower flux than expected below 4.6 μm . This effect is weaker, but still present in non-outburst data. The origin of

this likely instrumental distortion is unclear. To correct the spectra, radiance values above 4.2 μm were divided by a factor equal to $(1 - \lambda_{\text{ref}} \times s) + s \times \lambda$, $\lambda_{\text{ref}} = 4.5 \mu\text{m}$. For $s = 0.2$, this factor increases the radiance at 4.2 μm by a factor of 1.06, decreases the radiance at 5 μm by a factor of 1.10, whereas radiance values near 4.5 μm remain unchanged. Data acquired outside the outbursts suggest values $s = 0.1$ –0.2, whereas for outburst spectra $s = 0.2$ –0.4. Model fitting to spectra with this correction applied leads to higher values for T_{col} and $A(\theta)$, and lower values for S'_{col} . Uncertainties given in Table 2 take into account the range of values obtained for $s = 0$ –0.2 (appropriate for September 14 data and pre-outburst data), and $s = 0.2$ –0.4 (13 outburst September data). Other results presented in the paper come from spectra corrected with $s = 0.2$.

Some despiking was applied by ignoring spectral channels with a residual intensity with respect to a rough model fit larger than two times the rms noise. The rms noise corresponds to the standard deviation of radiance values measured across the residual spectrum. Since the statistical noise varies along the spectrum (data at short wavelengths are more noisy, see Fig. 1), it was computed over spectral windows, and assumed to be representative of the noise in these windows. The model has five free parameters. To find the optimum parameters, we computed contours for the variation of χ^2 as a function of T_{col} and α , using fine gridding. For each pair of values (T_{col}, α) , the optimum values of K_{scatt} , K_{therm} and $K_{\text{H}_2\text{O}}$ were determined using the χ^2 minimization algorithm of Levenberg–Marquardt. The best model fit is obtained for parameters corresponding to the minimum χ^2 in the (T_{col}, α) parameter space. The 1σ confidence level for these two parameters is derived from the contour at $\Delta\chi^2 = 2.3$, as described in Bevington & Robinson (1992). Uncertainties in $A(\theta)$ were computed taking into account the uncertainties in K_{therm} , K_{scatt} and T_{col} .

In order to best characterize the properties of the outburst material, a reference spectrum acquired before the beginning of the outburst was subtracted to the spectra. The first mini outburst of September 13 was not studied in detail, because of its faintness.

Figs 4 and 5 show the temporal evolution of T_{col} , S'_{col} and $A(\theta)$ retrieved from model fitting, with selected values reported in Table 2.

3.3 Retrieved dust scattering and thermal properties

3.3.1 Quiescent coma

Spectra obtained just before the outbursts yield $T_{\text{col}} \sim 300 \text{ K}$, $A(\theta) = 0.13$ and $S'_{\text{col}} \sim 2.5$ per cent/100 nm (Table 2), and similar values are measured when the outburst material has left the FOV.

A quantity used to characterize the scattering of cometary dust, and measured in numerous comets (Kolokolova et al. 2004) is the geometric albedo A_p times the phase function at phase angle α : $A_p(\alpha) = A_p \times j(\alpha)$, with $j(0) = 1$ (see Section 3.3). The total dust cross-section is derived from the thermal SED assuming an emissivity equal to 1, and this cross-section is then applied to the scattered intensity to derive an average $A_p(\alpha)$. We used this approach to derive $A_p(\alpha)$ at $\lambda = 2 \mu\text{m}$ from the VIRTIS-H spectra. Retrieved values are $A_p(\alpha) = 0.018$ and 0.021 for the pre-outburst spectra of September 13 and 14, respectively. A plot of $A_p(\alpha)$ as a function of time, with the same time sampling as in Figs 4 and 5 shows temporal variations. Considering only data points outside periods showing outburst-related signal excess, we find an average value $A_p(\theta) = 0.020 \pm 0.004$, where the error bar corresponds to the standard deviation of the sample. For these data points, we observe a positive




Figure 4. Colour temperature (A), 2–2.5 μm colour (B) and bolometric albedo (C) on 2015 September 13. Black symbols correspond to retrievals from total spectra, whereas blue symbols are for spectra with a reference pre-outburst spectrum removed. The radiance measured at 4.6 μm (with adapted scale) is shown in orange colour.

correlation between $A_p(\alpha)$ and T_{col} , with values of 0.025 reached for $T_{\text{col}} = 308\text{--}310$ K. A positive correlation with T_{col} is also observed for the bolometric albedo (Fig. 6B), from which we conclude that some data points are affected by outburst-related material.




Figure 5. Same as Fig. 4 at the time of the outburst of 2015 September 14.

3.3.2 Outbursts

The scattering and thermal properties of the dust particles in the outburst material strongly differ from those of the background coma (also referred to as the quiescent coma in this paper). The first acquisitions taken after the onset of the outbursts show a large increase in the colour temperature and bolometric albedo, and less red or




Figure 6. Correlation trends between colour temperature (T_{col}), 2–2.5 μm colour (S'_{col}) and bolometric albedo ($A(\theta)$). Black and red symbols are for September 13 and 14 data, respectively.

bluish dust colours. Spectra of the outburst material (i.e. with the background reference spectrum removed) show colour temperatures reaching ~ 550 K for the two investigated outbursts of September 13 (main and second mini ones), and ~ 640 K for the September 14 outburst. The three investigated outbursts all show negative blue colours, with an extreme value $S'_{\text{col}} \sim -10$ per cent/100 nm measured

at the peak of the September 14 outburst corresponding to a power index for the 2–2.5 μm reflectance of $\alpha_c = 2.30$. They also show similarly high bolometric albedos $A(\theta) \sim 0.6$. The three parameters show different behaviours as a function of time. The evolution of T_{col} and S'_{col} follow that of the light curves. They reach their most extreme values approximately at the time of the peak values of the radiances, returning then progressively to pre-outburst values. Several (at least three) local extrema are observed for these parameters during the September 13 main outburst (Fig. 4), confirming that the complex light curve of this event results from consecutive outbursts. Regarding $A(\theta)$, its temporal evolution follows that of light curves for the September 13 outbursts only. For the September 14 outburst material, measured $A(\theta)$ values remain high (and are even still increasing) after the decay of brightness has proceeded. This trend is at the origin of the very distinct light curves in the thermal and scattered wavelength ranges (Fig. 2).

To what extent are the light curves influenced by optical depth effects in the coma? The opacity can be estimated by ratioing measured radiances to the value expected for a fully opaque cloud. Assuming that the product of the normal geometric albedo times the phase function is equal to 0.02, as measured for the quiescent coma (Section 3.3.1), we find $\tau = 0.1$ at 2 μm for the peak brightness on September 14. This is a lower limit to the opacity, since outburst ejecta consist of bright dust particles (Section 4.3). The fact that light curves do not stall at their maximum value during some time interval is suggesting that opacity effects are not significant.

The temporal variability of the spectral properties is related to changes in the properties of the dust outburst material in the course of the event. The mean speed of dust grains detected by the Grain Impact Analyser and Dust Accumulator (GIADA) during the 2016 February 19 outburst is 6.5 m s^{-1} , pertaining to a mean radius of 180 μm (Grün et al. 2016). If we assume a speed dependence in $a^{-0.5}$, then grains with radii smaller than 10 μm (those contributing mainly to IR emission) have speeds exceeding 30 m s^{-1} . Their traveltime in the VIRTIS-H FOV is ≤ 6 s. Therefore, consecutive acquisitions do not sample the same material (providing projection effects are minimal). In Figs 4 and 5, the temporal evolution of the dust properties is presented with a time resolution ≥ 40 s, therefore each data point should pertain to distinct material.

4 INTERPRETATION WITH LIGHT-SCATTERING MODELLING

4.1 Modelling

The scattering and thermal properties of cometary dust depend on the particle composition and structure, and on the size distribution (Hanner 2003; Kolokolova et al. 2004). In order to analyse the 67P observations we used the Mie (Mie 1908) and Rayleigh–Gans–Debye (RGD; Tazaki et al. 2016, and references therein) scattering theories, combined with an effective medium theory in order to consider mixtures of different materials.

The GIADA experiment onboard the *Rosetta* spacecraft has suggested that most of the dust released from 67P consists of relatively compact particles with bulk densities between 10^3 and $3 \times 10^3 \text{ kg m}^{-3}$ and a mean porosity $P = 0.5$ (Rotundi et al. 2015; Fulle et al. 2015, 2016a; Della Corte et al. 2016). To model the infrared spectrum of these moderately porous grains, we used the Mie scattering theory. Mie theory considers homogeneous spheres, and provides reliable results in the Rayleigh regime (i.e. for size parameter $x = 2\pi a/\lambda \ll 1$, where a is the particle radius),

and for computing the emissivity and temperature of dust grains (Kolokolova et al. 2004).

The GIADA instrument detected short-lasting showers of low-density grains, resulting from the fragmentation of very fluffy, fractal-like particles (Fulle et al. 2015). Fractal-like particles were collected and imaged by the *Rosetta*'s Micro-Imaging Dust Analysis System (MIDAS) onboard *Rosetta* (Mannel et al. 2016). The large fractal aggregate ($\sim 20 \mu\text{m}$) examined by Mannel et al. (2016) has a fractal dimension $D = 1.7$ with subunits of mean diameter $\sim 1.5 \mu\text{m}$ that are expected to contain subunits of tenths of micrometre size (Bentley et al. 2016). Modelling the scattering properties of aggregates can be achieved by utilizing numerical methods such as the T-matrix method (TMM, for cluster spheres) or the discrete dipole approximation (DDA, for arbitrary shape particles). These methods need time-consuming computations, and because of this limitation, they have been applied so far only to small aggregates of a few micrometre size at most (Kolokolova et al. 2004; Kimura et al. 2016). The analysis of the VIRTIS spectra would require considering large aggregates. We made simulations for fractal aggregates under the hypothesis that the constituent subunits are Rayleigh scatterers and that the aggregates have a Balistic Cluster Cluster Aggregate (BCCA) topology. BCCA typically have a fractal dimension $D \leq 2.0$, and so resemble 67P fluffy grains. For such aggregates, the RGD theory can be used (Tazaki et al. 2016). Appendix B provides details on the performed RGD calculations, done for $D = 1.7$ and a subunit size of 100 nm.

Effective medium theories (EMT) allow us to calculate an effective refractive index for a medium made of a matrix (here assumed to be amorphous carbon) with inclusions of different composition (e.g. silicates). We used the Maxwell-Garnett mixing rule (Maxwell Garnett 1904). We defined the volume fraction of the inclusions in dust grains by the quantity q_{frac}^3 (Appendix A).

In order to simulate the infrared continuum emission of cometary dust, one has to compute the grain temperature as a function of grain size, which requires optical constants from the visible to far-infrared ranges (Appendix A). We considered the following materials for which these data are available: (1) amorphous carbon, (2) amorphous olivine, with a Fe:Mg composition of 50:50 consistent with the value in GEMS (glass with embedded metal and sulphides) found in IDPs, and in ISM dust (Keller & Messenger 2011), (3) amorphous Mg-rich pyroxene (Fe:Mg of 0:100), (4) Mg-rich crystalline olivine (spectral indices from a natural olivine) and (5) troilite FeS. Amorphous carbon is a strongly absorbing material in the visible and in the near-infrared. The refractory carbonaceous matter in cometary grains is likely polyaromatic, according to the known composition of chondritic porous stratospheric IDPs, of fine-grained fluffy Concordia Antarctic meteorites and of STARDUST grains that were not harshly modified during their capture in aerogel collectors (Sandford et al. 2006; Dobrică et al. 2011; De Gregorio, personal communication). Polyaromatic carbonaceous materials with small-sized polyaromatic units are however poorly absorbent in the range 1–5 μm (Quirico et al. 2016). However, carbonaceous matter in cometary grains is mixed up with metal and pyrrhotite (Fe_{1-x}S), which are believed to be at the origin of the low albedo of 67P nucleus (Capaccioni et al. 2015; Rousseau et al. 2017). Here, we used the optical constants of the less absorbent troilite (Henning & Stognienko 1996, and references therein), because no optical data are available for pyrrhotite. The optical properties of amorphous carbon and troilite finally fairly mimic a pyrrhotite+polyaromatic carbonaceous matter mixture, which represents the opaque component of cometary grains (see Engrand et al. 2016). The silicate component of cometary grains consists of crystalline and amorphous olivines

and pyroxenes (Wooden et al. 1999; Dobrică et al. 2011; Dobrică et al. 2012; Engrand et al. 2016). The references for the refractive indices are amorphous carbon (Edoh 1983), glassy (amorphous) silicates (namely MgSiO_3 pyroxene, and MgFeSiO_4 olivine, Dorschner et al. 1995) and Mg-rich natural crystalline olivine (Fabian 2001).

The nominal volume fraction of silicates in the grain is set to 0.34 ($q_{\text{frac}} = 0.7$), which is close to the value estimated for the grains of 67P by Fulle et al. (2016a) (0.33 excluding ices). The nominal model will consider amorphous olivine for the carbon/silicate mixture, which is relatively absorbent due to the presence of Fe, whereas other silicates are transparent.

In order to account for the porosity of the moderately compact grains, we followed the simple approach of Greenberg & Hage (1990), who applied the Maxwell-Garnett mixing rule with voids taken as the matrix and the mixture of constituent materials as the inclusions. The porosity is described by a fractal dimension D and the radius of the subunits a_{unit} :

$$P = 1 - (a/a_{\text{unit}})^{D-3}. \quad (8)$$

We used the values $D = 2.5$ and $a_{\text{unit}} = 100 \text{ nm}$. This fractal dimension is consistent with the constraint obtained for 67P compact grains by MIDAS (Mannel et al. 2016). The maximum porosity of the grains is set to P_{max} . Indeed, with the porosity law given by equation (8) the porosity increases with increasing size. We set $P_{\text{max}} = 0.5$, corresponding to the value established for the so-called compact grains detected by GIADA (Fulle et al. 2016a).

The size distribution of the dust particles is described by a power-law $n(a) \propto a^{-\beta}$. β is the size index and the particle radius a takes values from a_{min} to a_{max} . We set $a_{\text{max}} = 500 \mu\text{m}$ (large particles do not contribute significantly to IR radiation). For sizes larger than 30 μm , the size index is set to $\beta = 1.9$ (Merouane et al. 2016). We considered size distributions with β values from 2 to 5 and a_{min} from 0.1 to 20 μm .

Grain temperatures and synthetic spectra were computed, as described in Appendices A and B. The colour temperature, bolometric albedo and colour were retrieved from the synthetic spectra, as done for the VIRTIS-H spectra (Section 3.1). The temperatures of compact ($P = 0$) and moderately porous particles ($P_{\text{max}} = 0.5$) are plotted in Fig. 7. Fractal aggregates with $D = 1.7$ have temperatures equal to their constituent grains. This well established trend (Kimura et al. 2016, and references therein) is related to the fact that both the absorption cross-section and surface area of fractal agglomerates are proportional to the number of constituent grains in the limit of low fractal dimension. At 1.3 au from the Sun, the temperature of fractal grains ($D = 1.7$) is $\sim 100 \text{ K}$ for grains composed of transparent silicates and between 450 and 530 K for carbon–silicate mixtures and MgFeSiO_4 amorphous olivine (Fig. 7).

Spectral properties of the dust continuum radiation are plotted in Fig. 8, for the moderately porous ($P_{\text{max}} = 0.5$) carbon–silicate mixtures with $q_{\text{frac}} = 0.7$, and in Fig. 9 for the fractal aggregates. The upper-left plot in Figs 8 and 9 is the ratio $F(5 \mu\text{m})/F(2 \mu\text{m})$, where F is the intensity of the signal, in flux or radiance units. In VIRTIS-H non-outburst spectra this ratio is 0.8–0.9, whereas values of typically 0.4–0.5 characterize spectra of outburst material. Only models providing a good match to the observed bolometric albedo will be able to explain the relative intensity of the thermal emission with respect to scattered light.

4.2 Quiescent coma

The spectral properties of the 67P dust quiescent coma resemble those measured in other moderately active comets (Section 6). As




Figure 7. Grain temperature as a function of grain radius at $r_h = 1.3$ au. Dashed curves are for non-porous grains ($P = 0$) made of unique material: amorphous carbon (red), natural Mg-rich crystalline silicates (blue), amorphous MgSiO_3 pyroxene (orange) and amorphous olivine with Mg:Fe = 50:50 (green). Plain curves are for moderately porous ($P_{\max} = 50$ per cent, $a_{\text{unit}} = 100$ nm, $D = 2.5$) carbon/silicate mixtures ($q_{\text{frac}} = 0.7$ corresponding to a silicate volume fraction of 34 per cent) with same colour coding. Temperatures for mixtures of carbon with Mg-rich crystalline silicates are the same as for mixtures of carbon with amorphous MgSiO_3 pyroxene, so the curves are superimposed. The equilibrium temperature T_{equ} is shown as a black dash-dotted line.




Figure 8. Results from Mie-scattering calculations for moderately porous ($P_{\max} = 0.5$) carbon/olivine mixtures as a function of minimum size a_{\min} . The different colours correspond to different size indices β indicated in the top left figure. From left to right and top to bottom: ratio of the dust continuum radiation at $5 \mu\text{m}$ to the value at $2 \mu\text{m}$, bolometric albedo, colour at $2 \mu\text{m}$ and colour temperature. The model parameters are $q_{\text{frac}} = 0.7$, $a_{\text{unit}} = 100$ nm, $D = 2.5$, phase angle $\alpha = 90^\circ$. The Mg:Fe content of olivine is 50:50.

discussed in many papers in the literature, a 20 per cent colour temperature excess with respect to the equilibrium temperature ($S_{\text{heat}} \sim 1.2$) could be explained by the presence of micron-sized and smaller grains comprising absorbing material. The red colour implies that small grains with respect to the wavelength are not dominant, otherwise blue colours would be observed.

Fig. 8 shows that Mie scattering, for a moderately porous ($P_{\max} = 0.5$) mixture of amorphous olivine and amorphous carbon, is able




Figure 9. Results from Rayleigh-Mie-Debye calculations for fractal aggregates made of carbon/olivine mixtures. See caption to Fig. 8. The model parameters are $q_{\text{frac}} = 0.7$, $a_{\text{unit}} = 100$ nm, $D = 1.7$. The Mg:Fe content of olivine is 50:50.

to reproduce the properties of the 67P dust coma, providing submicrometric particles are considered. The size distribution cannot be uniquely constrained. Indeed, the spectral properties depend both on the slope of the size distribution β and minimum particle size a_{\min} . The sets $(a_{\min}, \beta) = (0.2 \mu\text{m}, 2.5)$ and $(0.5 \mu\text{m}, 3.0)$ provide satisfactory results for T_{col} , $A(\theta)$ and S'_{col} . Size distributions with $\beta \geq 3.5$ are not able to reproduce the observed red colour. The same constraints are obtained considering mixtures of carbon with a somewhat lower content of silicates, with fully transparent silicates, and considering pure-carbon grains. For non-porous grains ($P = 0$), the colour temperature is matched with the sets $(a_{\min}, \beta) = (0.1 \mu\text{m}, 2.5)$ and $(0.3 \mu\text{m}, 3.0)$, but $A(\theta)$ is overestimated by a factor of 2, whereas the colour is approximately matched. Grains devoid of dark absorbing material are excluded, as shown in Fig. 10. This figure presents how the spectral properties vary with each other, for comparison with the observed correlation plots shown in Fig. 6. It shows that, for pure silicatic grains or silicates mixed with FeS, size distributions consistent with the measured T_{col} yield neutral colours and bolometric albedos higher than measured.

The above interpretation does not consider fractal aggregates which are a significant component of the dust population in 67P coma, as discussed in Section 4.1. BCCA-type fractal aggregates reach high temperatures whatever their size (Fig. 9), so they could contribute to the 20 per cent colour temperature excess. However, they are not expected to contribute significantly to the scattered emission, since their spectrum exhibits a low bolometric albedo (Fig. 9). Della Corte et al. (2016) report the counts of compact particles compared with the number of fluffy fractal-like aggregates detected by GIADA from 2014 September to 2016 February. For the 2014 September to 2015 February period (bound S/C orbits), the relative number of fluffy aggregates is ~ 25 per cent. In the following months, this number was < 10 per cent (3 per cent at perihelion). The decrease is attributed to the low spacecraft potential at this time preventing charging and electrostatic fragmentation of the aggregates for detection with GIADA (Fulle et al. 2015; Fulle, personal communication). We performed calculations with a dust population containing both types of particles assuming they have the same size distribution. A relative fraction of fractal agglomerates of 3 per cent does not have significant impact on the dust continuum radiation.




Figure 10. Results from Mie-scattering calculations: correlation between spectral properties. The different colours are for different size indices β and correspond to those of Fig. 8. The different points for each β refer to different minimum sizes a_{\min} . Dotted symbols connected with dashed lines are for a carbon/olivine porous mixture with $q_{\text{frac}} = 0.7$. Stars connected with dashed lines are for porous olivine grains. The Mg:Fe content of olivine is 50:50. The model parameters are $a_{\text{unit}} = 100$ nm, $D = 2.5$, $P_{\text{max}} = 0.5$.

Fig. 11 shows results for a relative number of fluffy aggregates of 25 per cent. The VIRTIS-H spectra can be explained providing the minimum radius of the compact particles exceeds ~ 1 μm . For a minimum size $a_{\min} = 1$ μm , the required size index is $\beta = 2.5$. For $a_{\min} = 15$ μm , the model provides a good fit with $\beta = 2$. Large size indices (≥ 3.5) are excluded on the basis of the measured colour and




Figure 11. Results for relative fractions of 25 percent of fractal aggregates and 75 percent of moderately porous carbon/olivine mixtures ($P_{\text{max}} = 0.5$). See captions to Figs 8 and 9. The model parameters are $q_{\text{frac}} = 0.7$, $a_{\text{unit}} = 100$ nm, $D = 2.5$ for compact grains and $D = 1.7$ for fluffy grains. The Mg:Fe content of olivine is 50:50.

bolometric albedo. Neither COSIMA nor MIDAS provide evidence for abundant micrometre-sized particles in the coma of 67P (Mannel et al. 2016; Merouane et al. 2016). Therefore, we can conclude that the VIRTIS-H spectra are consistent with the constraints obtained by the *in situ* dust instruments onboard *Rosetta*: a dust population consisting of a mixture of compact particles and fluffy particles with a shallow size index and particle sizes larger than a few microns. In this picture, the dust superheating observed in comets is caused by fluffy aggregates. For 25 per cent of fluffy aggregates in number, their relative contribution to the scattered light is less than 1.5 per cent at 2 μm .

4.3 Outburst material

The IR continuum emission of the outburst material is characterized by high colour temperatures and bolometric albedo, and blue colours (Section 3.3, Figs 4 and 5). The high colour temperatures and blue colours imply the presence of Rayleigh-type scatterers in the ejecta, i.e. either very small grains or BCCA type agglomerates.

Let first consider the case of compact grains with $P_{\text{max}} = 0.5$. Figs 8 and 10 show that the high colour temperatures and blue colours are obtained in the case of large size indices β and small a_{\min} . The colour temperature is plotted as a function of the mean radius of surface equivalent sphere in the dust population a_{mean} (calculated from the weighted mean of the particle cross-sections) in Fig. 12. Colour temperatures of 600 K are reached for carbon/olivine grains with a mean radius of ~ 0.1 μm , whereas the colour temperature for silicatic grains of this size is ~ 530 K. Silicatic grains reach a high temperature because we are here considering olivine with a high Fe content which is a significantly absorbing material. For the steepest size distribution ($\beta = 5$), the colour reaches values ~ -10 per cent per 100 nm. Both the colour and colour temperature measured at the peak of brightness of the September 14 outburst are satisfactorily reproduced with a population of carbon/olivine grains, constituted almost uniquely of small grains with a mean radius of $a_{\text{mean}} \sim 0.1$ μm . However, the high bolometric albedo ~ 0.6 is not explained (Fig. 10B–C). The lower T_{col} and moderate bluish colour measured for the September 13 outburst implies somewhat larger




Figure 12. Results from Mie scattering calculations: colour temperature as a function of mean radius of surface equivalent sphere. Same colour coding as for Figs 8 and 10. Filled triangles are for a porous mixture of olivine and FeS, with 6 per cent of FeS in volume (only results for $\beta = 5$ are shown).

grains ($a_{\text{mean}} \sim 0.5 \mu\text{m}$ for carbon/olivine mixtures), but again the high bolometric albedo excludes grains with a significant content of strongly absorbing carbonaceous compounds.

Fig. 10 shows that spectra of silicatic grains (with the optical properties of Fe:Mg amorphous olivine) exhibit high bolometric albedos when small particles are dominant. Furthermore, the correlations observed between the spectral properties for pure olivine (Fig. 10) present striking similarities with those observed in the course of the outbursts (Fig. 6). This suggests that the outburst ejecta are comprising small and bright particles. The decrease of the colour temperature and colour shortly after the peak brightness suggests an increase of the mean particle size with time for the particles crossing VIRTIS FOV. The presence of silicatic grains devoid of organic material could be explained by the high grain temperatures causing sublimation of the organics.

Quantitatively, the September 13 outburst data are consistent with the silicatic grain hypothesis. However, large colour temperatures ($>600 \text{ K}$) are measured at the peak brightness of the September 14 outburst, whereas computed temperatures are $<530 \text{ K}$ for olivine grains. Several explanations are possible. First, we did not consider grains smaller than 100 nm in radius, whereas we cannot exclude their presence. These grains might reach higher temperatures than 100 nm grains, though this is not expected from model calculations (Lasue et al. 2007). In our model, 100 nm grains are compact ($P = 0$). Considering instead that these grains are aggregates, their temperature would be higher than the temperature of the equivalent sphere (Xing & Hanner 1997). Another possibility is that the spectral indices of amorphous olivine differ significantly from those of the refractory material of cometary grains. We performed Mie calculations with inclusions of FeS within an olivine matrix. For a volume fraction of 6 per cent of FeS consistent with the suggestion of Fulle et al. (2016a) for 67P grains, the colour temperature reaches 575 K (Fig. 12), which is not far from the extremum values measured during the September 14 outburst.

Could fractal agglomerates explain the outburst spectra? For carbon/amorphous olivine mixtures, the colour and colour temperature of their infrared spectrum match the measurement, but this is not the case for the bolometric albedo (Fig. 10). Calculations made for units of amorphous olivine provide a bolometric albedo <0.4 , i.e. a factor of 2 below the measured values. During 67P outbursts, MIDAS collected a high amount of micrometric grains (Bentley,




Figure 13. Reflectance spectra of outburst ejecta. Acquisitions 921–1051 (13 September 13.712 46–13.986 18 h UT) and 661–691 (14 September 18.905 40–18.968 21 h UT) were considered. The September 14 spectrum has been shifted vertically by $+0.002$. A median smoothing with dimension 6 has been applied. The reflectance is defined by $R(\lambda) = \pi I(\lambda) r_h^2 / F_{\odot}(\lambda)$, where $I(\lambda)$ is the measured radiance after removing the thermal radiation. The solid red line is the fitted reflectance over the full VIRTIS-H spectrum.

personal communication), in agreement with an ejecta population dominated by compact grains rather than aggregates. We performed calculations setting the maximum size of the fractal aggregates to $a_{\text{max}} = 1 \mu\text{m}$, and the bolometric albedo is still <0.4 .

Finally, the main contributors to the scattered and thermal parts of the spectrum could be distinct populations of grains. Cold and bright grains would essentially contribute to scattered light, whereas this is the opposite for warm and dark grains made of strongly absorbing material. These two populations of grains were found in the outburst ejecta of the extraordinary outburst of comet 17P/Holmes in 2007 October ($r_h = 2.45 \text{ au}$) (Yang et al. 2009). The near-IR spectra of the outburst ejectas showed strong absorption bands at 2 and $3 \mu\text{m}$ related to water ice (Yang et al. 2009).

Infrared signatures of ice are not detected in the VIRTIS-H outburst spectra. The $2 \mu\text{m}$ ice signature extends up to $2.2 \mu\text{m}$ (e.g. Yang et al. 2009), but the sensitivity in this wavelength range is low. In the 2.7 – $3.5 \mu\text{m}$ range, the dust continuum includes a significant contribution of the thermal radiation (~ 50 per cent or more), because the colour temperature is high. Therefore, detection of the $3 \mu\text{m}$ ice band, as an absorption feature in the dust scattered emission, is difficult. Reflectance spectra, obtained after subtracting the thermal radiation, do not show any absorption band. Fig. 13 shows outburst reflectance spectra averaging acquisitions in the time intervals 13 September 13.712 46–13.986 18 h UT and 14 September 18.905 40–18.968 21 h UT. The signal-to-noise ratio is 13–16 in the $3 \mu\text{m}$ ice band domain, implying a band depth less than ~ 10 per cent.

5 SPECTRAL SIGNATURES: H_2O , CO_2 AND ORGANICS

The VIRTIS-H spectra present strong H_2O and CO_2 fluorescence emission bands, at 2.67 and $4.26 \mu\text{m}$, respectively (Figs 1–3). The temporal evolution of their band areas does not provide evidence for outburst-related variations (Fig. 14). The variations observed for September 14 in Fig. 14B are mainly related to non-monotonic changes of the distance of the FOV to the comet centre during the time interval considered in the plot (ρ from 9.28 to 4.83 km




Figure 14. Temporal evolution of the areas of the H₂O 2.7 μm and CO₂ 4.26 μm bands at the time of the September 13 (A) and September 14 (B) outbursts. The time resolution is ~ 70 s. The spectral ranges used for computing the band areas are 2.55–2.74 and 4.20–4.35 μm , for H₂O and CO₂, respectively.

and then from 4.83 to 6.32 km, see Section 2). Indeed, the band areas are found to be well correlated with ρ , varying as $\propto \rho^{-0.7}$ and $\propto \rho^{-1.17}$ for H₂O and CO₂, respectively. These variations show that, although the H₂O and CO₂ emissions are affected by optical depth effects (Bockelée-Morvan et al. 2016), they respond to small changes in the column density. Observed 1σ fluctuations with respect to the mean band areas (for September 13), and the mean band areas corrected from distance (for September 14) are 3–5 per cent for H₂O and 4–12 per cent for CO₂, the larger numbers referring to the September 14 data. These numbers set an upper limit to the contribution of a possible gaseous counterpart to these dusty outbursts. The determination of upper limits on the gas loss rates is beyond the scope of this paper.

A broad-band extending between about 3.3 and 3.6 μm is detected in the outburst spectra (Fig. 15). The strength of the band correlates with the strength of the continuum emission. The selected time ranges for the outburst spectra shown in Fig. 15 correspond to maximum band strength. The band is not detected in pre-outburst spectra (Fig. 15). When averaging several VIRTIS-H data cubes acquired near perihelion, some intensity excess has been detected in this spectral region, especially from CH₄ lines (Bockelée-Morvan et al. 2016).




Figure 15. VIRTIS-H spectra of the 3.4 μm band observed on 2015 September 13 and 14. Labelled *outburst* spectra correspond to 13 September 13.712–13.792 h UT (middle) and 14 September 18.863–18.897 h UT (bottom). The spectrum labelled *quiescent* is the average of 850 acquisitions acquired before the September 13 outburst. The dust continuum emission has been removed. Outburst spectra include the contribution of the background coma, which is low. The *outburst* and *quiescent* September 13 spectra have been shifted by +0.003 and +0.006, respectively, in radiance units. Spectral channels found to be much more noisy than nearby channels have been removed.

This 3.3–3.6 μm band has been observed in several low-resolution cometary spectra (Bockelée-Morvan, Brooke & Crovisier 1995, and references therein), in particular during the outburst of 17P/Holmes (Yang et al. 2009). It corresponds to the signature of C–H stretching modes from organic species and hydrocarbons. Cometary spectra obtained at high spectral resolution showed that ro-vibrational lines of C₂H₆ and CH₃OH, as well as a few lines of OH and H₂CO (e.g. Dello Russo et al. 2006), and CH₄ (e.g. Mumma et al. 1996), are the main contributors to this broad-band for comets observed in quiescent states. Interestingly, the same strong line at 3.37 μm (2965–2968 cm^{-1}) is detected during the two 67P outbursts. Lines of C₂H₆ and CH₃OH fall within this range (Dello Russo et al. 2006), but stronger lines from these species are not observed.

We postpone the analysis of this band to a future paper, when data with an improved calibration will be available. The VIRTIS data suggest abundant release of organics during 67P outbursts. In 9P/Tempel 1 Deep Impact ejecta, enhanced C₂H₆ infrared emission was observed, higher than for CH₃OH and H₂O lines (Mumma et al. 2005; DiSanti et al. 2007).

6 SUMMARY AND DISCUSSION

We have presented an analysis of the 2–5 μm dust continuum radiation from comet 67P measured at 1.3 au from the Sun with the VIRTIS-H instrument. We focused on data acquired on 2015 September 13 and 14 at the time of two important 67P outbursts, with the aim to characterize the properties of the dust ejecta, in addition to those of the quiescent coma. A discussion of the results obtained in this paper is given below.

Comparison of the quiescent coma of 67P with other comets. The coma of 67P at 1.3 au from the Sun observed at a phase angle of $\sim 100^\circ$ exhibits a bolometric albedo of ~ 0.13 , a colour of ~ 2.5 percent per 100 nm in the range 2–2.5 μm , and a colour




Figure 16. Superheat factor S_{heat} (top) and bolometric albedo A (bottom) measured in comets (letters) compared to 67P values for the quiescent coma at 1.3 au from the Sun (this work). Letters correspond to comets: (a) 1P/Halley, (b) C/1975 N1 (Kobayashi-Berger-Milon), (c) C/1980 Y1 (Bradfield), (d) C/1989 X1 (Austin), (e) C/1995 O1 (Hale-Bopp), (f) C/1985 K1 (Machholz), (g) 23P/Brorsen-Metcalf, (h) C/2007 N3 (Lulin), (i) 9P/Tempel 1, (j) C/2009 P1 (Garradd), (k) C/1996 B2 (Hyakutake), (l) C/2012 K1 (PAN-STARRS), (m) Jupiter-family comets 69P/Taylor, 4P/Faye, 19P/Borrelly, 55P/Tempel-Tuttle, 24P/Schaumasse, (n) 103P/Hartley 2, (o) long-period comets reported in Sitko et al. (2004). Other measurements are from Gehrz & Ney (1992), Gicquel et al. (2012), Mason et al. (1998), Mason et al. (2001), Meech et al. (2011), Sitko et al. (2013), Woodward et al. (2011), Protospapa et al. (2014), Woodward et al. (2015). Blue colours are used for comet Hale-Bopp. A red colour is used for Jupiter-family comets.

temperature which is 20 per cent in excess with respect to the equilibrium temperature. Fig. 16 shows the bolometric albedo and superheat for a sample of comets. Within a few exceptions, 67P dust properties are in the mean of values measured in other comets, in particular Jupiter-family comets. Higher values for the bolometric albedo and superheat are measured for the bright comet C/1995 O1 (Hale-Bopp; Mason et al. 2001), whereas the hyperactive comet 103P/Hartley 2 shows an unusually low bolometric albedo of 0.06 at 53° phase angle (Meech et al. 2011) and a moderate superheat of 1.11 (Protospapa et al. 2014). The 2–2.5 μm colour measured in 67P is also typical (Jewitt & Meech 1986). We measured a value of 0.02 for the product of the geometric albedo times the phase function, consistent with previous values measured for 67P (Hanner et al. 1985) and with measurements in other comets (Hanner & Newburn 1989). Based on available data on the phase function

Schleicher (2010), the geometric albedo of the quiescent 67P dust coma is estimated to $A_p = 0.04$. Altogether, the scattering and thermal properties of the quiescent dust coma of 67P are representative of the properties measured for moderately active comets.

Dust properties in 67P quiescent coma. Mie scattering modelling shows that the measured scattering and thermal properties imply the presence of hot submicrometre-sized particles composed of absorbing material. This conclusion is consistent with previous interpretations of dust optical and infrared data (e.g. Hanner 2003; Kolokolova et al. 2004, and references therein). Fractal-like aggregates have been detected in significant quantities by the GIADA and MIDAS dust experiments onboard *Rosetta*, together with moderately porous compact grains (Fulle et al. 2015; Bentley et al. 2016; Mannel et al. 2016). Fractal aggregates with submicrometric absorbing subunits reach high temperatures, whereas they are not efficient scatterers. We showed numerically that such fluffy aggregates could be at the origin of the superheat, with the implication that submicrometric compact grains may be absent in cometary atmospheres.

Size distribution in 67P quiescent coma. We have obtained some constraints on the size index in 67P quiescent coma at 1.3 au from the Sun, having in mind model approximations and assumptions. Overall, assuming that compact grains are responsible for the superheat, a size index in the range 2.5–3 provides satisfactory results for both the superheat, colour and bolometric albedo. The low value $\beta = 2.5$ is obtained for a minimum particle radius a_{min} of 0.2 μm , whereas $\beta = 3$ is obtained for $a_{\text{min}} = 0.5 \mu\text{m}$. A somewhat shallower size index, in the range 2–2.5, is deduced when considering a mixture of compact particles and fractal aggregates, with ratio 75:25 in number. GIADA collections combined to OSIRIS data obtained at 2.0 au pre-perihelion are consistent with a size index of 2.2–2.6 (± 0.3) in the size range 80 μm to 2 mm (Rinaldi et al. 2017). GIADA collections for the 3.4–3.6 au pre-perihelion range show a similar size index (~ 2 , Rotundi et al. 2015). A power index of 1.9 ± 0.3 is deduced from the COSIMA collections in the size range 30–150 μm (Merouane et al. 2016). However, Fulle et al. (2016b) concluded to a steeper size index of 3.7 at perihelion from GIADA data, and found that the heliocentric evolution of the size index is consistent with ground-based observations of 67P dust tail and coma. The VIRTIS-H data seem to exclude such a steep size distribution at perihelion: both in the case of compact particles and compact/aggregates mixtures, the model calculations with $\beta = 3.5$ –4 provide neutral or slightly blue colours for the a_{min} values which provide colour temperatures consistent with the observed value (Figs 8 and 11). Therefore, though an evolution of the size distribution with heliocentric distance is possible, VIRTIS data suggest that it is not as strong as indicated by Fulle et al. (2016b).

Dust properties in 67P outburst ejecta. 67P underwent many dusty outbursts near perihelion (Vincent et al. 2016b). VIRTIS provides unique information on the properties of the dust ejecta. The outburst material displays high colour temperatures (up to 630 K) and blue colours (down to -10 per cent per 100 nm) in the IR. The outburst plume is also less red at 0.55 μm than the quiescent coma (Rinaldi et al., in preparation). The two former properties can be explained by the presence of very small grains. The constantly high (~ 0.7) bolometric albedo measured during the outburst sequence signs the presence of bright material in the outburst ejecta. This bright material could be silicatic dust devoid of organic material, or, alternatively, icy grains. The first hypothesis would mean that the warm temperatures experienced by the grains caused rapid degradation of the organic material. Insoluble organic matter (IOM) from meteorites, which shares commonalities with 67P refractory organics (Fray et al. 2016), disappears within ~ 90 s at 800 K and within

200 yr at 370 K (Kebukawa, Nakashima & Zolensky 2010), from which we derive that the time needed for thermal degradation at 600 K is ~ 3 h. This is too slow to alter 67P grains observed a few minutes after outburst onset. In presence of minerals, the thermal decomposition rate of IOM is observed to be larger, but the catalysing effect of minerals is efficient only for temperatures less than 600 K (Kebukawa et al. 2010).

The second interpretation would be consistent with the detection of the signature of icy particles with the Alice UV spectrometer during dusty outbursts (Steffl et al. 2016; Agarwal et al. 2017), though the infrared signature of water ice at 3 μm is not detected in VIRTIS-H spectra. In addition, studies of morphological changes associated with dusty outbursts showed that these outbursts result from cliff collapse (Pajola et al. 2017). Images of the collapsed edge of the Aswan cliff revealed the fresh icy interior of the comet, with an albedo at least six times higher than the nucleus surface (Pajola et al. 2017). Therefore, the presence of icy grains in the dust plume is not unexpected.

The very fine dust particles detected by VIRTIS in the outburst ejectas are possibly subunits of aggregates which fragmented or were superficially eroded during cliff collapse. Whether this is viable explanation needs quantitative investigations which are beyond the scope of this paper. The boulder size distribution in the Aswan talus, with a size index $\beta = 3.61$, shows that collapsing blocks on 67P produce predominantly small chunks (Pajola et al. 2017), as observed for rock avalanche deposits on Earth. Alternatively, it is also conceivable that these small grains are present in surface and subsurface layers. We have indeed some evidence for the presence of charged nanograins in the coma of 67P (Burch et al. 2015). Under normal activity, the release of submicrometre-sized particles is expected to be inefficient on cometary surfaces because the low gas pressure cannot overcome the relatively high tensile strength of small-sized aggregate layers (Gundlach et al. 2015). Gas loading of these small particles become possible if they are released into the atmosphere during the cliff collapse.

Mass-loss in 67P outbursts. Presently published estimations of the dust mass emitted in 67P outbursts are mainly derived from optical images obtained less than a few minutes after outburst onset (Knollenberg et al. 2016; Vincent et al. 2016b). These estimations make the assumption of a dust size distribution and geometric albedo similar to the quiescent coma values. However, the burst of brightness observed in scattered light is essentially from small and bright dust particles, as shown in this paper. Re-estimations in light of this finding have to be done.

Gaseous counterparts in 67P dusty outbursts. VIRTIS did not detect any increase in the H_2O and CO_2 column densities during the September 13–14 outbursts. This means that the triggering mechanism is not related to a large internal gas pressure, a mechanism proposed by Prialnik et al. (1993) for explosive outbursts. As already discussed, these outbursts were very likely caused by cliff collapse as for the one studied by Pajola et al. (2017). The lifetime of 0.1–1 μm icy grains is ~ 300 –800 s for dirty grains, and $> 10^4$ s for pure ice grains (Beer, Podolak & Prialnik 2006; Gicquel et al. 2012). These long lifetimes may be one of the reasons why H_2O vapour was not detected in the VIRTIS-H outburst spectra. On the other hand, abundant release of organics is suggested by the detection of the 3.4 μm band in outburst spectra, possibly related to the thermal decomposition of complex organics present in grains, or to volatile organics originating from the collapsed wall.

67P outburst properties: comparison with other comets. One of the best studied outbursts is the huge outburst of comet 17P/Holmes at 2.4 au from the Sun. The ejecta displayed both a large superheat

($S_{\text{heat}} = 2.0$) and a blue spectral slope in the IR (-3 per cent per 100 nm) (Yang et al. 2009) which showed temporal variations attributed to changes in particle size. In addition, Ishiguro et al. (2010) measured a large geometric albedo 2 d after the outburst. The 2 and 3 μm water ice signatures were detected, with a depth for the 3 μm band of ~ 30 per cent, i.e. much larger than the limit we obtained for 67P. A broad emission feature was also detected at 3.36 μm (Yang et al. 2009). Hence, there is strong similarity between 67P and 17P outburst ejecta. Other outbursting or fragmenting comets where an increase of superheat, bolometric albedo or blue colours have been measured include 1P/Halley, C/1996 B2 (Hyakutake), C/1999 S4 (LINEAR) (Gehrz et al. 1995; Mason et al. 1998; Bonev et al. 2002). We also note similarities with the ejecta cloud produced by the Deep Impact experiment on 9P/Tempel 1 composed of both icy grains and hot small-sized dust (e.g. Sunshine et al. 2007; Gicquel et al. 2012).

To conclude, infrared observations with VIRTIS are providing unique information on the dust properties in 67P quiescent coma and outburst plumes, which are complementary to those from *in situ* and other remote sensing instruments onboard *Rosetta*. Future studies will benefit from coordinated multi-instrument data analyses.

ACKNOWLEDGEMENTS

The authors would like to thank the following institutions and agencies, which supported this work: Italian Space Agency (ASI; Italy), Centre National d'Etudes Spatiales (CNES; France), Deutsches Zentrum für Luft-und Raumfahrt (DLR; Germany), National Aeronautic and Space Administration (NASA; USA). VIRTIS was built by a consortium from Italy, France and Germany, under the scientific responsibility of the Istituto di Astrofisica e Planetologia Spaziali of INAF, Rome (IT), which lead also the scientific operations. The VIRTIS instrument development for ESA has been funded and managed by ASI, with contributions from Observatoire de Meudon financed by CNES and from DLR. The instrument industrial prime contractor was former Officine Galileo, now Selex ES (Finmeccanica Group) in Campi Bisenzio, Florence, IT. The authors wish to thank the Rosetta Science Ground Segment and the Rosetta Mission Operations Centre for their fantastic support throughout the early phases of the mission. The VIRTIS calibrated data shall be available through the ESA's Planetary Science Archive (PSA) Web site. With fond memories of Angioletta Coradini, conceiver of the VIRTIS instrument, our leader and friend. DBM thanks L. Kolokolova for useful discussions.

REFERENCES

- Agarwal J. et al., 2017, MNRAS, in press
- Beer E. H., Podolak M., Prialnik D., 2006, *Icarus*, 180, 473
- Bentley M. S. et al., 2016, *Nature*, 537, 73
- Bevington P. R., Robinson D. K., 1992, *Data Reduction and Error Analysis for the Physical Science*, 2nd edn. WCB/McGraw-Hill, New York
- Bockelée-Morvan D., Brooke T. Y., Crovisier J., 1995, *Icarus*, 116, 18
- Bockelée-Morvan D. et al., 2016, MNRAS, 462, S170
- Bonev T., Jockers K., Petrova E., Delva M., Borisov G., Ivanova A., 2002, *Icarus*, 160, 419
- Burch J. L., Gombosi T. I., Clark G., Mokashi P., Goldstein R., 2015, *Geophys. Res. Lett.*, 42, 6575
- Capaccioni F. et al., 2015, *Science*, 347, aaa0628
- Coradini A. et al., 2007, *Space Sci. Rev.*, 128, 529
- Davidsson B. J. R. et al., 2016, *A&A*, 592, A63
- Della Corte V. et al., 2016, MNRAS, 462, S210

- Dello Russo N., Mumma M. J., DiSanti M. A., Magee-Sauer K., Gibb E. L., Bonev B. P., McLean I. S., Xu L.-H., 2006, *Icarus*, 184, 255
- DiSanti M. A., Villanueva G. L., Bonev B. P., Magee-Sauer K., Lyke J. E., Mumma M. J., 2007, *Icarus*, 187, 240
- Dobbins R. A., Megaridis C. M., 1991, *Appl. Opt.*, 30, 4747
- Dobrić E., Engrand C., Quirico E., Montagnac G., Duprat J., 2011, *Meteorit. Planet. Sci.*, 46, 1363
- Dobrić E., Engrand C., Leroux H., Rouzaud J.-N., Duprat J., 2012, *Geochim. Cosmochim. Acta*, 76, 68
- Dorschner J., Begemann B., Henning T., Jaeger C., Mutschke H., 1995, *A&A*, 300, 503
- Drossart P. et al., 2000, in Strojnik M., Andresen B. F., eds, *Proc. SPIE Vol. 4131, Infrared Spaceborne Remote Sensing VIII*. SPIE, Bellingham, p. 78
- Edoh O., 1983, PhD thesis, Univ. Arizona
- El-Maarry M. R. et al., 2017, *Science*, 355, 1392
- Engrand C. et al., 2016, *MNRAS*, 462, S323
- Fabian D., Henning T., Jäger C., Mutschke H., Dorschner J., Wehrhan O., 2001, *A&A*, 378, 228
- Feldman P. D. et al., 2016, *ApJ*, 825, L8
- Fink U. et al., 2016, *Icarus*, 277, 78
- Fray N. et al., 2016, *Nature*, 538, 72
- Fulle M. et al., 2015, *ApJ*, 802, L12
- Fulle M. et al., 2016a, *MNRAS*, 462, S132
- Fulle M. et al., 2016b, *ApJ*, 821, 19
- Gehrz R. D., Ney E. P., 1992, *Icarus*, 100, 162
- Gehrz R. D., Johnson C. H., Magnuson S. D., Ney E. P., Hayward T. L., 1995, *Icarus*, 113, 129
- Gicquel A., Bockelée-Morvan D., Zakharov V. V., Kelley M. S., Woodward C. E., Wooden D. H., 2012, *A&A*, 542, A119
- Greenberg J. M., Hage J. I., 1990, *ApJ*, 361, 259
- Grün E. et al., 2016, *MNRAS*, 462, S220
- Gundlach B., Blum J., Keller H. U., Skorov Y. V., 2015, *A&A*, 583, A12
- Hanner M., 2003, *J. Quant. Spectrosc. Radiat. Transfer*, 79, 695
- Hanner M. S., Newburn R. L., 1989, *AJ*, 97, 254
- Hanner M. S. et al., 1985, *Icarus*, 64, 11
- Henning T., Stognienko R., 1996, *A&A*, 311, 291
- Ishiguro M. et al., 2010, *ApJ*, 714, 1324
- Jewitt D., Meech K. J., 1986, *ApJ*, 310, 937
- Kebukawa Y., Nakashima S., Zolensky M. E., 2010, *Meteorit. Planet. Sci.*, 45, 99
- Keller L. P., Messenger S., 2011, *Geochim. Cosmochim. Acta*, 75, 5336
- Kimura H., Kolokolova L., Li A., Lebreton J., 2016, in Kokhanovsky A., ed., *Light Scattering Reviews*, Vol. 11. Springer-Verlag, Berlin, p. 363
- Knollenberg J. et al., 2016, *A&A*, 596, A89
- Kolokolova L., Hanner M. S., Lvasseur-Regourd A.-C., Gustafson B. Å. S., 2004, in Festou M. C., Keller H. U., Weaver H. A., eds, *Comets II*. Univ. Arizona Press, Tucson, AZ, p. 577
- Lasue J., Lvasseur-Regourd A. C., Fray N., Cottin H., 2007, *A&A*, 473, 641
- Mannel T., Bentley M. S., Schmied R., Jeszenszky H., Lvasseur-Regourd A. C., Romstedt J., Torkar K., 2016, *MNRAS*, 462, S304
- Mason C. G., Gehrz R. D., Ney E. P., Williams D. M., Woodward C. E., 1998, *ApJ*, 507, 398
- Mason C. G., Gehrz R. D., Jones T. J., Woodward C. E., Hanner M. S., Williams D. M., 2001, *ApJ*, 549, 635
- Maxwell Garnett J. C., 1904, *Phil. Trans. R. Soc. A*, 203, 385
- Meech K. J. et al., 2011, *ApJ*, 734, L1
- Merouane S. et al., 2016, *A&A*, 596, A87
- Mie G., 1908, *Ann. Phys.*, 330, 377
- Mumma M. J., DiSanti M. A., Dello Russo N., Fomenkova M., Magee-Sauer K., Kaminski C. D., Xie D. X., 1996, *Science*, 272, 1310
- Mumma M. J. et al., 2005, *Science*, 310, 270
- Pajola M. et al., 2017, *Nat. Astron.*, 1, 0092
- Prialnik D., Egozi U., Ban-Nun A., Podolak M., Greenzweig Y., 1993, *Icarus*, 106, 499
- Protopapa S. et al., 2014, *Icarus*, 238, 191
- Quirico E. et al., 2016, *Icarus*, 272, 32
- Rinaldi G. et al., 2016, *MNRAS*, 462, S547
- Rinaldi G. et al., 2017, *MNRAS*, this issue
- Rotundi A. et al., 2015, *Science*, 347, aaa3905
- Rousseau B. et al., 2017, *Icarus*, in press
- Sandford S. A. et al., 2006, *Science*, 314, 1720
- Schleicher D., 2010, Available at: asteroid.lowell.edu/comet/dustphase_details.html
- Shi X. et al., 2016, *A&A*, 586, A7
- Sitko M. L., Lynch D. K., Russell R. W., Hanner M. S., 2004, *ApJ*, 612, 576
- Sitko M. L. et al., 2013, in 44th Lunar Planet. Sci. Conf., *The Grain Albedo of Comet C/2009 P1 (Garradd)*. Abstract #1154
- Steff A. J. et al., 2016, American Astronomical Society, DPS Meeting #48, 110.03
- Sunshine J. M., Groussin O., Schultz P. H., A'Hearn M. F., Feaga L. M., Farnham T. L., Klaasen K. P., 2007, *Icarus*, 190, 284
- Tazaki R., Tanaka H., Okuzumi S., Kataoka A., Nomura H., 2016, *ApJ*, 823, 70
- Vincent J.-B. et al., 2016a, *A&A*, 587, A14
- Vincent J.-B. et al., 2016b, *MNRAS*, 462, S184
- Wooden D. H., Harker D. E., Woodward C. E., Butner H. M., Koike C., Witteborn F. C., McMurtry C. W., 1999, *ApJ*, 517, 1034
- Woodward C. E. et al., 2011, *AJ*, 141, 181
- Woodward C. E. et al., 2015, *ApJ*, 809, 181
- Xing Z., Hanner M. S., 1997, *A&A*, 324, 805
- Yang B., Jewitt D., Bus S. J., 2009, *AJ*, 137, 4538

APPENDIX A: SCATTERED AND THERMAL EMISSION

The scattered solar flux and thermal emission from a population of dust particles are respectively given by

$$F_{\text{scatt}}(\lambda) = K \frac{F_{\odot}(\lambda)}{4\pi r_h^2} \int_{a_{\min}}^{a_{\max}} C_{\text{scatt}}(a, \lambda) p(a, \lambda, \theta') n(a) da, \quad (\text{A1})$$

$$F_{\text{therm}}(\lambda) = K \int_{a_{\min}}^{a_{\max}} B(\lambda, T(a)) C_{\text{abs}}(a, \lambda) n(a) da, \quad (\text{A2})$$

with

$$B(\lambda, T) = \frac{2hc^2}{\lambda^5} \frac{1}{e^{hc/\lambda kT} - 1}. \quad (\text{A3})$$

The scattering and absorption cross-sections are related to the scattering and absorption efficiencies $Q_{\text{scatt}}(a, \lambda)$ and $Q_{\text{abs}}(a, \lambda)$:

$$C_{\text{scatt}}(a, \lambda) = Q_{\text{scatt}}(a, \lambda) G(a), \quad (\text{A4})$$

$$C_{\text{abs}}(a, \lambda) = Q_{\text{abs}}(a, \lambda) G(a). \quad (\text{A5})$$

In these equations, a is the particle radius (from a_{\min} to a_{\max}), $n(a) = a^{-\beta}$ is the size distribution, $T(a)$ is the grain temperature and $G(a) = \pi a^2$ is the particle cross-section. K is a constant which sets the number of grains in the FOV. The solar irradiance F_{\odot} at $r_h = 1$ au from the Sun is modelled by a blackbody at 5770 K. The quantity $p(a, \lambda, \theta')$ is the phase function, where θ' is the scattering angle, which satisfies the normalization condition:

$$\frac{1}{2} \int_0^{\pi} p(a, \lambda, \theta') \sin(\theta') d\theta' = 1. \quad (\text{A6})$$

At thermal equilibrium, the temperature $T(a)$ can be computed from the balance of the solar energy absorbed at visual wavelengths and

the energy radiated in the infrared (Kolokolova et al. 2004):

$$\frac{1}{r_h^2} \int F_{\odot}(\lambda) C_{\text{abs}}(a, \lambda) d\lambda = 4\pi \int B(\lambda, T(a)) C_{\text{abs}}(a, \lambda) d\lambda. \quad (\text{A7})$$

Mie-scattering theory provides $Q_{\text{scatt}}(a, \lambda)$, $Q_{\text{abs}}(a, \lambda)$ and $p(a, \lambda, \theta')$ scattering parameters for homogeneous spheres made of material with refractive index m .

APPENDIX B: RAYLEIGH-GANS-DEBYE THEORY

The RGD theory is a simple and robust method to compute the scattering and thermal emission of fractal dust aggregates where the component subunits are Rayleigh scatterers (Tazaki et al. 2016). This theory has been thoroughly investigated in the field of atmospheric science, to model, e.g. the optical properties of soot particles. It assumes that multiple scattering inside the aggregates can be ignored, so that the light scattered by the subunits are superposed, taking into account the phase differences between light rays. The RGD theory, its conditions of validity, and comparisons with results obtained with the more rigorous TMM are presented in details in Tazaki et al. (2016). When the conditions of validity are satisfied, then the phase matrix element S_{11}^{agg} is related to that of the subunits S_{11}^{unit} through:

$$S_{11}^{\text{agg}}(\theta') = N^2 S_{11}^{\text{unit}}(\theta') S(q), \quad (\text{B1})$$

where N is the number of subunits and $S(q)$ is a structure factor, with $q = (4\pi/\lambda)\sin(\theta'/2)$.

The phase matrix element S_{11} is related to the scattering efficiency and phase function through

$$S_{11}(\theta') = \frac{\pi}{\lambda^2} G(a) Q_{\text{scatt}}(a, \lambda) p(a, \lambda, \theta'). \quad (\text{B2})$$

The structure factor $S(q)$ is a function of the fractal dimension D , the number of monomers, and a factor which describes the degree of correlation between the light rays scattered by the subunits. We used the expression $S(q)$ given by equation (24) of Tazaki et al. (2016).

The number of subunits is given by

$$N = k_0 \left(\frac{a}{a_{\text{unit}}} \right)^D, \quad (\text{B3})$$

where the size of the aggregate a corresponds here to the radius of gyration R_g (equal to $(3/5)^{1/2}$ times the characteristic radius for spherical aggregates). Calculations were made for $D = 1.7$ and $a_{\text{unit}} = 100$ nm. BCCA aggregates tend to have $D = 1.9$ – 2 and $k_0 = 1.03$, so we adopted this value for k_0 . $S(q)$ has the limits $S(q) = 1$ for $qR_g \ll 1$ and $S(q) = (qR_g)^{-D}$ for $qR_g \gg 1$.

The angle-averaged scattering cross-section is given by (Dobbins & Megaridis 1991)

$$C_{\text{scatt}}^{\text{agg}} = N^2 G(a_{\text{unit}}) Q_{\text{scatt}}(a_{\text{unit}}, \lambda) \left[1 + \frac{4}{3D} \left(\frac{2\pi R_g}{\lambda} \right)^2 \right]^{-D/2}. \quad (\text{B4})$$

The absorption cross-section (that is the absorption efficiency times the aggregate cross-section) is equal to the total geometric cross-section of the subunits multiplied by the absorption efficiency for a single subunit (Dobbins & Megaridis 1991):

$$C_{\text{abs}}^{\text{agg}} = NG(a_{\text{unit}}) Q_{\text{abs}}(a_{\text{unit}}, \lambda). \quad (\text{B5})$$

Therefore, the temperature of the fractal aggregates is equal to the temperature of the subunits which can be computed from equation (A7).

The criteria of validity for the RGD method are $|m - 1| \ll 1$, $2x_{\text{unit}}|m - 1| \ll 1$ and $2x_{\text{agg}}|m_{\text{eff}} - 1| \ll 1$, where x_{unit} and x_{agg} are the size parameters of the subunits and aggregates, respectively (Tazaki et al. 2016). m is the refractive index of the subunits. m_{eff} is the effective refractive index of the aggregates computed with the Maxwell-Garnett formula with the vacuum taken as the matrix component (Greenberg & Hage 1990). Those criteria show that the RGD method provides the most reliable results for almost transparent monomers. In our computations with amorphous carbon mixed with silicates, the three quantities $|m - 1|$, $2x_{\text{unit}}|m - 1|$ and $2x_{\text{agg}}|m_{\text{eff}} - 1|$ are ~ 1.1 , 0.7 and 0.6 , respectively, at $\lambda = 2$ μm . Therefore, the validity conditions are only marginally satisfied for this opaque mixture. The comparison with TMM calculations made by Tazaki et al. (2016) suggests that we should expect reliable results within 10 per cent or so for the scattered emission as far as BCCA particles are concerned.

Tazaki et al. (2016) showed that the RGD theory agrees with the TMM within 10 per cent for aggregates with $N < 1024$, which corresponds to an aggregate characteristic radius ~ 4 μm . It was found that the relative error with respect to the TMM grows slightly with the number of monomers due to the overlapping of monomers along the line of sight. Tazaki et al. (2016) suggest that the relative errors should saturate for large N because the degree of overlap is saturating for large N . With respect to TMM, the RGD theory tends to overestimate the scattered intensity, so it overestimates the geometric albedo of the particles.

From the equations above, we see that, for a given aggregate size, the scattered intensity increases with increasing fractal dimension (i.e. decreasing porosity).

This paper has been typeset from a $\text{\TeX}/\text{\LaTeX}$ file prepared by the author.